#### Capsule Summary

The Kefauver Schoolhouse is adjacent to U.S. Route 40 Alt. and Hollow Road Creek about one mile east of Middletown. It is a two-story, front gabled frame building three bays wide and three bays deep. The house was constructed in the early-to-mid nineteenth century. Windows consist of 1/1, double-hung, aluminum sash replacements. The only remaining original window is a central attic gable window on the front of the house which is an original wood 2/2 double-hung sash. The entire house is clad with vinyl siding, and the gables and soffit have been covered with aluminum. A full-length front porch with shed roof dates from the mid-to-late twentieth century has a concrete floor and round aluminum posts. The roof has been replaced with asphalt shingles.

The original section of the interior of the house consists of a main living room which has a fireplace. To the left of the living room are several small rooms that are the result of recent renovations which divided the one large room to provide a closet, a bathroom and a laundry room. The first floor of the rear addition consists of a one room kitchen. The second story was not accessible, but the owner stated that the second story layout is identical to the first floor. The house has a full basement. Floor and sill beams are a mixture of hand hewn and sawn beams. The basement floor is dirt.

The Kefauver Schoolhouse appears to have been built in the mid-nineteenth century, probably by Henry R. Smeltzer. It is depicted on Titus' map of Middletown as belonging to Smeltzer in 1873 (Titus 1873). Smeltzer also owned Motter's Tavern (F-4-30) and another dwelling on the north side of the National Road directly across from these structures (no longer extant). Given its apparent original one-room design, with a single wide room with a fireplace at the center of the rear wall, the building may have been originally constructed as a schoolhouse although no period maps depict it as such. In 1882, Smeltzer's widow sold this property (and others, including Motter's Tavern) to Daniel Kefauver (Liber AF-5:54). It is likely that the Kefauver's constructed the addition soon after buying the property. The Kefauvers were prominent local residents who owned a number of farms and dwellings, and at least one grist mill in the Middletown area.

The original section was only one room wide and one room deep on both the first and second floors. It was expanded in the 1880s to include the ell addition which was also one room on each floor. Some time after the construction of the addition, a two-story porch was added to the inset of the ell on the east elevation. The interior of the house was significantly altered around 1980 by its previous owner. Alterations included the partitioning of the single front room to make room for a bathroom, closet, and laundry room. The kitchen, which is in the rear addition, was remodeled around the same time,. The second story is identical to the first story, according the Mrs. McDonald (access to the second story was not possible).

The Kefauver Schoolhouse, although it may be representative of a mid-nineteenth century rural Maryland schoolhouse, has undergone window replacements, exterior renovations, and interior remodeling that has compromised its integrity of materials, design, workmanship, and feeling, and no longer possesses adequate integrity to be eligible for the National Register.

# Maryland Historical Trust State Historic Sites Inventory Form

Survey No. F-4-135

Magi No.

DOE yes no

1. Name	(indicate preferred name	e)					
historic	Kefauver Schoolhouse						
and/or common	David McDonald F	David McDonald Residence					
2. Location							
street & number	4241 Route 40-A (	Old National Pike)		not for	publication		
city, town	Middletown	X vicinity of 6th	congression	onal district			
state	Maryland county		Frederick				
3. Classi	fication						
Category	Ownership	Status	Present U				
district	public	x occupied		culture morsial	museum park		
x building(s) structure	<u>x</u> private both	unoccupied work in progress		·			
site	Public Acquisition	Accessible		rtainment	x private residence religious		
object	in process	x yes: restricted		ernment	scientific		
	being considered	yes: unrestricted			transportation		
	x not applicable	no	milita	ary	other:		
4. Owner	of Property	(give names and mailin	g addresses of <u>a</u>	all owners)			
name	David McDonald						
street & number	number 4241 Route 40-A		telephone	no.:			
city, town	town Middletown state and zip co		e: <b>M</b> D 217	69			
	on of Legal De						
				lib			
courthouse, registr	ry of deeds, etc. Frede	erick County Courthouse		liber			
street & number	100 V		folio				
city, town	r, town Frederick			MD 21	701		
6. Repres	sentation in E	xisting Historica	al Surve	ys			
title							
date		fede	eral state	e county	local		
dato		1ede	nai state	county	10041		
'spository for surv	ey records						
city, town		·	state	)			

7. Descrip	otion		Survey No. F-4-135
Condition excellent x good	deteriorated	Check one unaltered x altered	Check one original site moved date of move
fair	unexposed		

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

The Kefauver Schoolhouse is adjacent to U.S. Route 40 Alt. and Hollow Road Creek about one mile east of Middletown. It is a two-story, front gabled frame building three bays wide and three bays deep. The house rests on a fieldstone foundation. There is a central brick chimney at the junction of the original rear of the house and a circa 1880 addition. Windows consist of 1/1, double-hung, aluminum sash replacements. The only remaining original window is a central attic gable window on the front of the house which is an original wood 2/2 double-hung sash. The entire house is clad with vinyl siding, and the gables and soffit have been covered with aluminum. A full-length front porch with shed roof dates from the mid-to-late twentieth century has a concrete floor and round aluminum posts. The roof has been replaced with asphalt shingles.

The original section of the interior of the house consists of a main living room which has a fireplace. To the left of the living room are several small rooms that are the result of recent renovations which divided the one large room to provide a closet, a bathroom and a laundry room. The first floor of the rear addition consists of a one room kitchen. The second story was not accessible, but the owner stated that the second story layout is identical to the first floor.

The house has a full basement. Floor and sill beams are a mixture of hand hewn and sawn beams. The basement floor is dirt.

o. Sigiiii	icance							July Cy 140	7. 1 4 100
Periodprehistoric1400-14991500-15991600-16991700-17991800-18991900-	Areas of Signif	-prehistoric -historic e	con con ecc x edu enc exp ind	justify bel mmunity pla nservation onomics ncation gineering ploration/se ustry ention	anning _ _ _ _ _ _	law literatui military music philoso			religion science sculpture social/ humanitarian theater transportation other (specify)
Specific dates	ca. 1885		Builder/	Architect	unknown				
Applic	cable Criteria: and/or able Exception: of Significance:	xA A natio	B B onal	x C C state	D D local	E	F	G	

Survoy No.

Prepare both a summary paragraph of significance and a general statement of history and support.

The Kefauaver Schoolhouse appears to have been built in the mid-nineteenth century, probably by Henry R. Smeltzer. It is depicted on Titus' map of Middletown as belonging to Smeltzer in 1873 (Titus 1873). Smeltzer also owned Motter's Tavern (F-4-30) and another dwelling on the north side of the National Road directly across from these structures (no longer extant). Given its apparent original one-room design, with a single wide room with a fireplace at the center of the rear wall, the building may have been originally constructed as a schoolhouse although no period maps depict it as such. In 1882, Smeltzer's widow sold this property (and others, including Motter's Tavem) to Daniel Kefauver (Liber AF-5:54). It is likely that the Kefauver's constructed the addition soon after buying the property. The Kefauvers were prominent local residents who owned a number of farms and dwellings, and at least one grist mill in the Middletown area.

The present owner, Mrs. McDonald related that Noah Kefauver always maintained that the Kefauver family constructed the building specifically for use as a schoolhouse for the family's children. Mrs. McDonald dated the original structure to about 1885, explaining that there is a date at the base of the original rear exterior chimney (now enclosed by a later addition) bearing a date of "1880 something". As the house appears on the 1873 Titus map as belonging to Henry R. Smeltzer, it is more likely that the that the date on the fireplace refers to the addition, which coincides roughly with the purchase of the house by the Kefauver family. It is likely that the construction that Noah Kefauver recalled was that of the addition, and not the original structure.

The front porch was added sometime in the mid -to-late twentieth century. It is constructed of a concrete floor, aluminum posts, and aluminum trim. The roof of the porch is covered with architectural style fiberglass shingles

The original section was only one room wide and one room deep on both the first and second floors. It was expanded in the 1880s to include the ell addition which was also one room on each floor. Some time after the construction of the addition, a two-story porch was added to the inset of the ell on the east elevation. The interior of the house was significantly altered around 1980 by its previous owner. Alterations included the partitioning of the single front room to make room for a bathroom, closet, and laundry room. The kitchen, which is in the rear addition, was remodeled around the same time,. The second strory is identical to the first story, according the Mrs. McDonald (access to the second story was not possible).

Exterior alterations included the addition of vinyl siding and aluminum fascia and soffits in 1998, and all of the original 2/2 wood windows have been replaced with 1/1 vinyl replacement sashes. The only remaining original window appears to be the front attic window.

The Kefauver Schoolhouse, although it may be representative of a mid-nineteenth century rural Maryland schoolhouse, has undergone window replacements, exterior renovations, and interior remodeling that has compromised its integrity of materials, design, workmanship, and feeling, and no longer possesses adequate integrity to be eligible for the National Register.

## 9. Major Bibliographical References

Survey No F-4-135

Mrs. McDonald, oral interview with property owner. January, 1999

Frederick County Deeds, Frederick County Courthouse, Frederick, Maryland.

Titus, C.O.

1873 Atlas of Frederick County.

10. Geogr	aphical Data			·			
Acreage of nominate Quadrangle name	ed property less than 1 Middletown, Maryland	_	Quadrangle scale 1:24000				
UTM References A Zone Easting	Do NOT complete UTM references  Northing	B Ea	Ll_sting	Northing			
cl l		DLL L					
EL L		FLL] L					
G		H					
Boundaries for property lines to	escription and justification the Kefauver Schoolhouse consist of Rou o the south and east. These boundaries a counties for properties overlapping sta	re those to whic	h the owner hol				
Jate	code	county		code			
state	code	county	code				
11. Form	Prepared by						
name/title	David C. Berg						
organization	Greenhorne & O'Mara		date	1/22/99			
street & number	9001 Edmonston Road	·····	telephone	(301) 220-1879			
city or town	Greenbelt		state	Maryland			

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust

DHCP/DHCD

100 Community Place

Crownsville, MD 21032-2023

410-514-7600

## **Continuation Sheet**

Survey No. F-4-135

#### Maryland Comprehensive Historic Preservation Plan Data

Geographic Organization:

Piedmont

Chronological/Development Periods:

Agricultural-Industrial Transition (1815-1870),

Industrial/Urban Dominance (1870-1930)

Historic Period Themes:

Architecture, Education

Resource Type:

Building

Historic Environment:

Rural


Historic Function

Schoolhouse, Residence


Known Designers/Architects:

None

House Plan Sketch (1st Floor)



Note: Second Floor Not Accessable





MIHP# F-4-135 Kefauver Schoolhouse Frederick County, Maryland David C. Berg 1/11/99 LOCATION of NegAtives: MO SAPO Kefauver Schoolhouse, North Elevation #1 of 4



Kefauver Schoolhouse Frederick County, Maryland David C. Berg 1/11/99 Location of Negatives: MO SHPO Kepnuver Schoolhouse, East Elevation #20F4

MIHP# F-4-135



MIHP # F-4-135 KefAuver School house Frederick County, Maryland David C. Berg 1/1/99 Location of Negatives: MO SHPO Kefaurer Schoolhouse West Elevation #3 of 4



Kefaurer Schoolhouse Frederick County, Maryland David C. Berg 1/11/99 LOCATION OF NegAtives: MO SHPO Kefaurer Schoolhouse, Kitchen , First Floor, Facing N. #4 of 4